




ROOM LIST	
ROOM No.	ROOM NAME
1	HEAD OFFICE
2	GENERAL KITCHEN STORAGE
3	REFRIGERATOR
4	VEGETABLE PREPARATION
5	EXTERNAL STORAGE
6	KABAB COOKING
7	HVAC ROOM
8	CORRIDOR
9	KITCHEN STAFF ROOM
10	KITCHEN AREA
11	WASHING
12	GARBAGE AREA
13	LOCKERS
14	J.C.
15	SHOWER
16	TOILET
17	ELEC. ROOM
18	STAFF AIR LOCK
19	WEIGHT AREA
20	ENTRANCE AREA

- GENERAL NOTES:**
- 1- THIS DRAWING IS VALID ONLY FOR PHONE SYSTEM LAYOUT.
  - 2- INSTALLATION HEIGHT OF TELEPHONE JACK SOCKETS SHALL BE 0.3m ABOVE FINISHED FLOOR IN OFFICE & STAFF ROOM AREAS.
  - 3- INSTALLATION HEIGHT OF WALL MOUNTED TELEPHONE SET SHALL BE 1.5m ABOVE FINISHED FLOOR .
  - 4- CONDUITS USED IN ALL AREAS SHOULD BE HOT DEEP GALVANIZED (HDG) AND FLUSH MOUNTED OR SURFACE MOUNTED ACCORDING TO TYPE OF SOCKET AS SPECIFIED IN DRAWING.
  - 5- SIZE OF CONDUITS SHOUL BE:
    - PG13.5 FOR 6x2x0.6 JY(st)Y
    - PG16 FOR 10x2x0.6 JY(st)Y
    - PG36 FOR 30x2x0.6 J-2Y(st)2Y
  - 6- CABLING CAN BE DONE BY PULLING THE CABLE ON THE LOW CURRENT CABLE TRAY AND MOVING TO THE NEAREST SOCKET WITH CONDUIT.
  - 7- PHONE JACK SOCKET POSITION SHOWN IN THIS DRAWING COULD BE MODIFIED ACC. TO SITE DETAILS OR COORDINATION WITH OTHER SYSTEMS BY CONTRACTOR.
  - 8- INSTALLATION HEIGHT OF TELEPHONE TERMINAL BOX SHOULD BE 2.5m ABOVE FINISHED FLOOR AND PVC TYPE AS SURFACE MOUNTED.



00		1399/04/26		IFA				
REVISION NO.		DATE		DISCRIPTION				
<div>شرکت توسعه آهن و فولاد گل گهر Golgohar Iron &amp; Steel Development Co. G.I.S.D.Co</div> <div></div>				PROJECT: <b>Golgohar Steel Project</b>				
				PROJECT DRAWING No.		REV		
DRAWING TITLE : <b>DRP KITCHEN</b> TELEPHONE SYSTEM LAYOUT								
<div><div>شرکت مهندسی بارسو <b>BARSOO</b> ENG. CO. CONSULTING and PROJECT MANAGEMENT</div></div> <div>BARSOO DRAWING No.</div> <div>157DEGB1045003</div>				DESIGNED	SIGNATURE	DATE	SCALE	SIZE
				DRAWN	M.OMRANIAN	1399/04/20	NTS	A 1
				CHECKED	M.OMRANIAN	1399/04/27	PROJECT REF. NO.	
				APPROVED	A.GOUDARZI	1399/04/31		